

TECHNO FINANCE PROPOSAL

3.72 KW HYBRID SOLAR SYSTEM

BASIC *System*
Layout

SYSTEM RATING

3.72 Kw

SYSTEM TYPE

Hybrid

PV RATING

3.72 Kw (Jinko Bifacial)

INVERTER

06 Kw SolarMax Orion



Customer Details			Quotation: 3.72 KW Hybrid System		Proposal Details :		
Customer Name : Ahsan Raza					Proposal Number : 721		
Region : Multan					Validity : 02 days		
Contact : 0312 6347622					Date :	25/03/2026	
No.	Description			Unit	Qty	Unit Cost	Total Cost
1	Power Generation System						
1.1	PV Modules	Jinko 620W N-Type Bifacial 12 Years Material Warrenty & 25 years Performance Warranty		Panel	6	46.5	172,980
1.2	Solar Inverter	Solarmax Orion 6KW		EA	1	0	0
1.3	Structure	14 Guage L3 Frames with SS NUT Bolts		EA	2	9000	18,000
1.4	DC Cables	4MM2, Stranded DC XLPO Cable; Vr = 1.5 KV Make : Fast Cables		MTR	60	300	18,000
1.5	AC Cables	7/44 PVC Cable (Single Core), Vr = 1KV Make : Fast Cable		MTR	20	280	5,600
1.6	Balance of Plant	AC Circuit Distribution	Distribution Box, AC Breaker, Voltage Protection Device, Surge Protection Device Make : Tomzen	Set	1	15,000	15,000
		DC Circuit Distribution	PV Breakers, Surge Protection Devices Make : Tomzen or Equivalent	Set	1	5500	5500
		Misc.	Ducts & Conduits (Make : Popular / Adam gee / Equivalent); IP65 Water Proof MC4 Connectors	Set	1	14000	14000
1.8	Battery	Lithium Ion Battery (51V, 100AH, 5KWH) 5 Year Replacement Warranty		EA	0	0	0

No.	Description			Unit	Qty	Unit Cost	Total Cost
1	Power Generation System						
1.9	Earthing	AC /DC Circuit Earth	Boring till Moisture Level (Dia 4-6") Eathing Powder or Gel (Marshal/equi.) Earthing Rod (3Ft) 16AWG Earthing Coil; 2.5MM2 Earth Wire Earth Resistance < 50hm	Job	0	22000	0
		Lightning Protection	01 Standard Surge Arrestor Insulator Earthing (Specification Similar to AC/DC Earth)	Job	0	30000	0
A	Total Cost of Power Generation System						249080
2	Installation and Transportation and Misc. Jobs						
2.1	System Designing Provision of Material Comissioning and Testing of Complete System System warranty upto 01 Years			Job	3720	4.5	16,740
2.2	Transportation of Offered Equipment to the Site			Job	1	10000	10000
2.3	Concrete Block Pad (L x W x H: 8" * 8" * 8") Material and Civil Works			Pads	12	850	10200
B	Total cost of Installation and Transportation and Misc. Jobs						36,940
3	Net Metering						
3.1	Net-Metering Process Fee Including Green Meter			Job	0	0	0
3.2	Cut of Accessories (Cut off Breaker, Metal DB, 16MM2 4 Core Cable 1-MTR) (will be charged only if required)			Set	0	0	0
C	Total Cost Net Metering						0
Total Project Cost							286020
Discount Offered							186020
Total Discounted Cost							270,000

General Terms and Condition:

Payment Terms:

1. All payments shall be made to the following account:
 - Account Name: **Raitex Solar System Private Limited**
 - Account Number: **2032314221445**
 - Bank Name: **UBL**
2. Payment Terms are as follows
 - Payment Milestone – I: 80 % Advance at the time of contract signing
 - Payment Milestone – III: 20 % Physical Completion of Solar System
3. If the order is cancelled by the client after PO issuance / Contract Signing, Raitex Solar System (Pvt) Ltd. reserves the right to charge a cancellation fee (20% of the selling price of the equipment offered)

Customer Scope:

1. Customer will be responsible to provide site access to Raitex team.
2. Customer will be responsible for the safety and security of equipment, once delivered to the Project Site.
3. Customer will be responsible for provision of strong Internet (Wi-Fi router / dongle device) near Inverter for Mobile app configuration.
4. Customer or his representative shall be available at the site for kickoff meeting with the execution team at the initiation of physical work.

Technical:

5. Grid-Tied system will Shut down during load shedding / power outage even at day time.
6. **Hybrid Inverters operating without Net Metering and Batteries are anticipated to consume 1-3A Current from Wapda for their proper functioning.**
7. **Production Level of Hybrid Inverters working without Batteries will be significantly reduced during the Load shedding Period / unavailability of grid.**
8. Any Additional Scope delivered upon the explicit request of the customer shall be charged separately and transaction shall be made prior to delivery of requested services.
9. All prices are subject to change without prior notice due to currency fluctuations
10. Delivery timeline of the project shall be 1 week

Warranty Terms and Conditions

Scope of Warranty:

1. Raitex Solar Systems warrants the troubleshooting and rectification of the system (if required) free of cost for the duration of the warranty period (6 Months), subject to the terms outlined below.
2. Warranty services shall be claimable only in cases where system production is halted. No other claims shall be entertained
3. Raitex warranties shall be considered null and void if maintenance, troubleshooting, or system repairs are carried out by any third-party service providers not authorized by Raitex.
4. Raitex warranties do not cover damages resulting from natural disasters, including but not limited to hailstorms, windstorms, flooding, or other acts of God.
5. Raitex will respond to and provide assistance within 24 - 36 hours of the initial contact made by the customer.
6. Raitex shall not be held liable for any delays in rectification or replacement of equipment that falls under OEM warranty. the customer agrees that any such delays will not hold Raitex accountable, and the responsibility for such delays lies with the OEM.
7. Warranty claims of inverters shall only be entertained if fall under the warranty T&C of Inverter's OEM
8. The warranty is non-transferable and applies only to the original customer as specified in the contract. Any changes in ownership or transfer of the system to a third party will void the warranty unless specifically agreed upon by Raitex.

Maintenance Agreement Offer

The Solar System, like any device, requires a degree of maintenance. The regular maintenance and check-ups of the system by a specialized technician are necessary to ensure reliable and sustained operation of your System Components. Raitex offers a long term (3-5 Years) Preventive Maintenance Packages, over additional charges, covering following key areas:

1. Solar Modules Cleaning.
2. Solar Modules Output testing (VOC / ISC testing)
3. Inspection of MC4, Cables, Cable Terminations, structures, Control Box, Batteries and Inverter.
4. Cables Continuity/Resistance testing.
5. Insulations resistance testing
6. Inverter Std. Preventive Maintenance (Cleaning, Configuration and performance testing)
7. L2/L3 Structure Integrity Assessment and tightness
8. Production Curve Analysis
9. Batteries Backup Testing
10. Control Box Cleaning and Functional Testing.
11. Earth Resistance Testing & Earth Circuit Continuity Testing

ACKNOWLEDGEMENTS

I ACKNOWLEDGE THAT I HAVE READ ALL THE TERMS AND CONDITIONS OF THIS PROPOSAL AND I FULLY UNDERSTAND WHAT IS STATED HEREIN. I EXPRESSLY AGREE TO ALL THE TERMS AND CONDITIONS SET OUT HEREIN AND TO ADHERE TO ALL PAYMENTS OBLIGATIONS AND OTHER ANCILLARY OBLIGATIONS.

Customer Signature: _____

CNIC: _____

Raitex Representative Signature: _____

Amount Received: _____